


Yonge subway extension: concept plan and profile





The yonge subway extension is part of a GTA-wide transit system





Metrolinx | the big move



Yonge subway extension ~ a key priority

Top 15 Priorities

Within the first 15 years of the Regional Transportation Plan's implementation, the top 15 priorities for early implementation are:

- Yonge subway extension to Richmond Hill Centre
- Eglinton rapid transit from Pearson Airport to Scarborough Centre
- Upgrade/extension of Scarborough rapid transit line
- Finch/Sheppard rapid transit from Pearson Airport to Scarborough Centre and Meadowvale
- Express Rail on Lakeshore line from Hamilton to Oshawa
- Rapid transit in Hamilton from McMaster University to Centennial Parkway
- Hurontario rapid transit from Port Credit to Brampton
- 403 Transitway from Mississauga City Centre to Renforth Gateway
- Rail link between Union Station and Pearson Airport
- Rapid transit service along Hwy 2 in Durham
- Improvements/extension of GO Rail service to Bowmanville
- Early phases of bus rapid transit service on Dundas St in Halton and Peel
- Viva rapid transit on Hwy 7 and Yonge St through York Region
- Brampton's Queen St Acceleride
- Spadina subway extension to Vaughan Corporate Centre



What we studied

To develop recommendations for the Yonge subway extension project, we assessed options and obtained public input for:

- Alignment
- Numbers and locations of stations

VIVA York Region M TORONTO

- How the subway will cross the East Don River
- The location of the terminus of the subway at Highway 7, its features and how it works











Where are we today?





What are the major phases of planning and building a subway?

	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017
Complete Functional Design										
Provincial Project Approval [6 months duration] October 2008 – April 2009										
Project Notice To Proceed Initial Capitalization May 2009										
Project Management Governance AFP Set-up: 1 year, mid 2010										
Property CEAA [12 months duration] 2009-2011										
Design Engineering [48 months overall duration] 2010-2013 [multiple projects starts and completion]										
Construction [66 months overall duration] 2011-2016 [multiple projects starts and completion]										
Subway System Commissioning [1 year duration] Throughout 2016										
In-service 2016/2017										

Key targets

- > project begins: 2009
- > design/engineering: 2009
- > construction: 2011
- > open: 2016/2017

VIVA York Region M TORONTO



What comes with a subway?

passenger pick up and drop off



parking facility



substation






emergency exit building







Yonge subway capacity improvements



VIVA York Region MTORONTO





How is a subway built?





























Construction principles

Our goal is to minimize disruption and inconvenience to the community during subway construction. Every effort will be made to:

- Use tunnelling, wherever possible
- Ensure the design of subway related structures is sensitive to existing neighbourhoods
- Maintain property access at all times
- Ensure appropriate number of lanes of traffic are always available in the peak direction
- Minimize the size of construction work areas
- Contain work areas to maintain community and pedestrian safety
- Provide timely construction updates to the community
- Complete construction as quickly as possible




transit benefits

just ahead



Yonge subway extension: station planning





Screening criteria

Existing densities		80	85	110	80	
Planned densities†		110 - 120	280 - 520	145 - 180	100 - 130	
Transportation connection	ו	1	1			
Natural environment		1	1	✓	1	
Cultural environment		1	1	✓	1	

Tail track: 🔀 Cross track: 🗙

* Some reconstruction of existing tail tracks will be required

VIVA York Region MTORONIO

** 4-bay after Finch LRT is completed

† Persons and jobs per hectare

Not to scale

Longbridge/ Langsattf X Richmond Hill Centre -900m -1:				
			x	
Tunnel Cut & Cover Tunnel Cut & Cover	900 m			
	Tunnel	Cut & Cover	Tunnel	Cut & Cover

1			
			28-bay bus terminal
			Proposed 407 Transitway
		1. en ?	Richmond Hill GO Rail
	PPUDO		PPUDO
	Approx. 2000 to 2500 park-n-ride		
			Substation

30	40
144 - 266	295 - 550
1	 Image: A start of the start of
1	1
1	✓



Preliminary construction methodology

While significant lengths of the subway extension will be tunnelled, the construction of subway stations and special track work structure is done using the cut and cover method.




Legend

Subway station
 Cut and cover
 Tunnelling
 Bridge construction
 Tail tracks
 Launch shaft
 Exit shaft

VIVA York Region TORONTO



Cummer/Drewry station




Legend

	Subway station
	Subway line
E	Entrance
00000	Limit of surface elements
	Underground walkway
***	Full property acquisition
	Partial property acquisition for surface elements only
V	Vent structure
B	Bus loop





Steeles station





Steeles station | level by level

1 station overview all levels



3 bus platform 1 level below street



Clark station



Legend

	Subway station
	Subway line
I	Electrical substation
E	Entrance
	Limit of surface elements
	Underground walkway
***	Full property acquisition
	Partial property acquisition for surface elements only
V	Vent structure






East Don River crossing

• Heritage features will be designed into the bridge in consultation with the community.

















East Don River proposed traffic staging


• Careful removal of existing culvert and embankments will minimize local disruption.



2 stage 2 temporary northbound lanes on partially constructed bridge



3 stage 3 final bridge in service







Crossing the East Don River



South aerial view from York Condominium 300 Artists rendering ~ concept only




1 Restore the valley to its natural state

- 2 Level Yonge Street to provide continued access to adjacent sites
- 3 Ensure the bridge design includes heritage features in context with the community
- 4 Ensure lighting is designed to be sensitive to adjacent uses in the community
- 5 Provide a safe pedestrian environment to cross between the heritage community north and south of the bridge
- 6 Meet Ministry of Environment guidelines for attenuating traffic and subway noise



Royal Orchard station



Legend

	Subway station
	Subway line
I	Electrical substation
E	Entrance
	Limit of surface elements
	Underground walkway
***	Full property acquisition
	Partial property acquisition for surface elements only
V	Vent structure





Langstaff/Longbridge parking

Design features that address community concerns:

- Noise buffers
- Maintaining a green corridor connection
- Bio swales
- Sustainable treatments for the parking area

















Conceptual design, to be further developed in consultation with the community.



Langstaff / Longbridge station






Legend

	Subway station
	Subway line
I	Electrical substation
E	Entrance
00000	Limit of surface elements
	Underground walkway
***	Full property acquisition
	Partial property acquisition for surface elements only
V	Vent structure
c	Limit of PPUDO, Park 'n' Ride, and associated roads.





Richmond Hill Centre alignment





vivnext

Major project costs

major project elements	cost M\$			
stations and area facilities	stations and area facilities			
Finch improvements	\$5			
Cummer/Drewry	\$70			
Steeles	\$195			
Clark	\$70			
Royal Orchard	\$65			
Langstaff/Longbridge	\$85			
Richmond Hill Centre	\$160			
tunnels, special structures and operating systems		\$600		
subway trains		\$240		
storage and maintenance facilities for subway trains		\$110		
engineering and other costs		\$675		
property		\$125		
project cost estimate, 2008 dollars	\$2.4	billion		











Next steps

December 2008

- Continue to post draft technical reports on vivayork.com for review and comments
- Draft Environmental Project Report

January 2009

- Issue Notice of Completion
- Submit Environmental Project Report to Ministry of the Environment for 30-day public review

February 2009

• Ministry of the Environment review period [up to 35 days]

March 2009

Issue Statement of Completion

Spring 2009

Project ready to proceed



